MULTI-AMP®
BIDDLE™
MEGGER®

GE Rental/Lease
Biddle CB-832
Rnt# 12970
1-800-GE-RENTS GE-11

Electrical Test Equipment
Measuring Instruments
Testing and
Training Services

AVO™

AVO INTERNATIONAL

multi-amp CORPORATION

4271 Bronze Way Dallas, Texas 75237-1088 U.S.A.
Ph. (214) 333-3201 Telex 163548 MULAM DL Fax (214) 333-3533

Multi-Amp Canada, 445 Finchdene Square, Scarborough, Ontario, M1X 1B7
Ph. (416) 298-6770 Telex 065-25453 Fax (416) 298-7214

INSTRUCTION MANUAL

For

HIGH CURRENT TEST SET

MODEL CB-832

SERIAL NO._____

It is essential that this instruction book be read thoroughly before putting the equipment in service.

Part Nº 12470
Rev. 1 8/15/91

IMPORTANT

The information and data contained within this instruction manual are proprietary with MULTI-AMP Corporation. The equipment described herein may be protected by one or more U.S. letters patent. MULTI-AMP specifically reserves to itself all rights to such proprietary information as well as all rights under any such patent, none of which is waived by the submission of this instruction manual to anyone.

The recipient, if a Government agency, acknowledges that this instruction book and the equipment described were procured with "Limited Rights" to technical data as described in ASPR 9-203 (b).

Copyright MULTI-AMP Corporation, 1983,1984 ,1985,1986,1987,1988,1989,1991

Part N° 12470
Rev. 1 8/15/91

TABLE OF CONTENTS

SECTION			PAGE
I.	INTRODUCTION		1
	A.	Specifications	bulletin
	B.	General Information	1
	C.	About This Manual	1
	D.	Safety Precautions	2
II.	THEORY OF OPERATION		3
	A.	Description of Controls	3
	B.	Selection of Output Terminal	5
	C.	Selection of Output Leads	6
	D.	Overload Capacity	6
III.	TEST PROCEDURES		8
	A.	Maintenance of Motor Overload Relays	8
		1. Planned Maintenance Program	10
		2. Time Delay	11
		3. Instantaneous Element	13
	B.	Maintenance of Molded Case Circuit Breakers	15
		1. Planned Maintenance Program	15
		2. Thermal Element	16
		3. Instantaneous Element	17
		4. Ground Fault Element	19
IV.	SERVICE DATA		21
	A.	Service and Repair Order Instructions	22
	B.	Preparation for Reshipment	23
	C.	Operational Errors/Troubleshooting	23
	D.	Warranty	25
V.	SCHEMATICS		26

SECTION I

INTRODUCTION

GENERAL INFORMATION

The Multi-Amp Model CB-832 is a self-contained test set which incorporates a variable high current output and appropriate control circuitry and instrumentation for testing thermal , magnetic, or solid-state motor overload relays, molded-case circuit breakers and ground fault trip devices.

ABOUT THIS MANUAL

This manual provides the user with all of the necessary information for complete working understanding of the CB-832 test set. It is divided into five main sections.

SECTION I	Gives a description of the test set. Gives basic guidelines on the different applications performed with it.
SECTION II	Is a detailed guide to all the controls and operating modes of the CB-832. This section is by far the most important for understanding how to use the test set.
SECTION III	Contains selected test procedures for motor overload relays and molded case circuit breakers.
SECTION IV	This section contains a troubleshooting guide and service and repair information.
SECTION V	This section contains a schematic drawing of the test set.

Part Nº 12470
Rev. 1 8/15/91

SAFETY PRECAUTIONS

Every consideration has been given to the design and construction of the Multi-Amp Model CB-832 Portable High Current Test Set to make it a safe piece of test equipment as well as one that is accurate, reliable, and easy to use.

WARNING

The Model CB-832 is not designed for use on energized circuits. For the safety of the operator and protection of the instrument, do not connect it to circuits that are energized. This includes circuits that could become energized during the course of a test procedure utilizing this instrument.

It must be remembered that the test set is capable of producing voltage and current levels that can be deadly if personnel come in contact with them.

For safe operation, it is absolutely essential that the technician properly and effectively ground (earth) the test set. This is accomplished by connecting the input line cord to a properly grounded receptacle.

CAUTION

The input voltage of this instrument is not selectable. All the units are shipped from the factory set up for operation from either a nominal 115 volt or 230 volt source. If the unit is to be used on a voltage source different than the nameplate specifies, major changes in the test set are required. It is necessary for the technician to contact the factory to obtain the necessary parts and instructions before attempting to change the input voltage of the test set.

The CB-832 should be properly operated by qualified personnel who have familiarized themselves with the test set and thoroughly read the instruction manual provided with it.

If questions arise concerning the care, operation, maintenance or application of the test set, contact the Multi-Amp Corporation for assistance.

SECTION II

THEORY OF OPERATION

DESCRIPTION OF CONTROLS

This section of the instruction manual describes the functions of all the various control switches, etc. which are located on the control panel of the Model CB-832. All controls are clearly marked and logically grouped so that continual reference to the instruction manual should not be necessary after the operator has become acquainted with the operation of the test set.

POWER ON/OFF Switch — Controls input power to the test set. The self-protected switch resets after an overload, when placed in the OFF position. Displays will light when the switch is ON.

MAIN FUSE — Protects power output circuit of CB-832 against overloads.

CONTROL FUSE — Protects instrumentation and control circuitry against overloads.

OUTPUT CONTROL — Variable autotransformer provides continuous non-stepped output from a variety of current-rated terminals. Output system is controlled by a combination of timer STOP MODE and OUTPUT MODE Switch positions.

OUTPUT ON Lamp — Lights whenever output control circuit is energized.

OUTPUT Terminals: — A combination of the COMMON terminal and any one of the three current-designated terminals provides an output circuit. Refer to other sections of the text for an explanation of the output characteristics of these terminals.

NOTE: The current designation of these terminals has no bearing on the actual current output capability of each. Much higher currents can be achieved depending on test circuit impedance and duration of the test.

OUTPUT MODE Switch — Initiates the output circuit in conjunction with the appropriate Timer STOP MODE Switch position.

MOMENTARY	Momentary on position with spring return to OFF. Output will remain energized as long as switch is held in MOMENTARY position and is de-energized when released. Timer starts and stops in the same manner. Used for jogging the output circuit.
MAINTAIN	Maintained on position with spring return to OFF. Output will remain energized until appropriate STOP MODE function occurs, switch is moved to OFF position or current drops below threshold requirement.
OFF	Test set input power remains energized but output current remains de-energized and timer will not count.
AMMETER	LED displays show the numeral one in the left most position when the meter is over-ranged.
RANGE SWITCH	Decimal of display shifts one digit to the right for each increase in range selection.
DISPLAY MODE Switch	Selects either the NORMAL or MEMORY mode of the ammeter.
NORMAL	Ammeter updates reading continually as long as the output is energized. Reading is lost when the output is de-energized.
MEMORY	Ammeter retains the highest peak value attained during current output operation above 8% of the full scale of range selected. Reading is retained until the output is reinitiated or RANGE SWITCH position is changed.
TIMER	Automatically resets each time output is reinitiated.
CYCLES/SEC. Switch	Selects cycles or seconds mode.
CYCLES Position	The timer counts in whole cycles and uses the power input line frequency as timing reference.
SEC. Position	The timer counts in two selectable increments and uses an internal 10kHz oscillator as timing reference.

.01/.001 Switch — Selects one of two counting increments available for the timer SEC. mode.

NOTE: Changing the position of the CYCLE/SEC. Switch (or the .01/.001 Switch while in the SEC. position) during timer operation will produce erroneous readings.

CONTACTS Binding Posts — Circuit controls output and timer in the normally open or normally closed positions of the STOP MODE Switch.

NOTE: Do not connect CONTACTS binding posts to an energized circuit.

STOP MODE Switch — Selects either current actuated position to stop the current output and timer, or either of the two external contact stop mode positions.

NORM. OPEN — With CONTACTS binding posts connected to normally open contacts, output circuit will remain energized and timer will continue to run until contacts close.

NORM. CLOSED — With CONTACTS binding posts connected to normally closed external contacts, output circuit will remain energized and timer will continue to run until contacts open.

CURRENT — Timer will initiate only when the output circuit is completed and a threshold current of approximately 8% of full scale of ammeter range selected is exceeded. Timer will continue to run until output circuit opens, current drops below threshold level or output is de-energized.

SELECTION OF OUTPUT TERMINAL

Three output terminals at various voltage and current ratings are provided to adapt the CB-832 to a wide variety of test circuit impedances.

The Multi-Amp Model CB-832 circuit breaker test set has three current output terminals to provide a wide range of current-voltage capabilities. The terminal with the lower current rating provides an output with the highest voltage for testing devices of low current requirements but with high impedance characteristics. This tap also has the highest output resolution capable of fine current adjustments. The highest current rated output terminal provides high current availability for testing devices of high current requirements of relatively low impedance. This tap offers the highest resolution for voltage applications. Should the current required for the

device to be tested exceed the ability of the lowest tap or the impedance of the device to be tested require more voltage to "push" the current than is available from the highest current tap, the medium range current tap can be utilized to provide the current or voltage necessary to perform the desired test. Selection of the output terminal depends entirely on the characteristics of the device to be tested, therefore, proper selection will require some experimentation and will be easier as familiarity increases.

NOTE: There is no relationship between the ammeter ranges and the ratings of the output terminal. All ammeter ranges can be used in conjunction with any of the output terminals.

SELECTION OF OUTPUT LEADS

Model CB-832 is equipped with output connecting bars for attachment of the high current test leads provided or any others suitable for the test application.

The following information on the selection of output leads will provide the user with a guide for choosing the proper test leads for his application.

Due to the voltage drop from the inductive reactance of the test circuit, a significant loss of current will result for each inch of test lead. Therefore, when choosing test leads, the length and size of leads chosen will determine the maximum available test current. It is worthwhile to sacrifice cross section of test leads for the sake of reducing length. Every inch of lead that can be eliminated provides worthwhile increase in available test current. Heating is not a significant problem in testing, even though the leads become hot. Paralleling of sufficient cables provides higher test currents. Each cable can be fitted with a compression lug on each end, then bolted to the output terminals or stab board of the test set and the breaker.

The two cables between the test set and the breaker should be twisted together or bundled with tape or cord to maintain the close proximity which minimizes inductive reactance.

OVERLOAD CAPACITY

Model CB-832 is rated at 1.75 kVA output and is equipped with three output terminals, each capable of supplying its rated current. The current rating of these output terminals may be exceeded for short durations provided the voltage rating is sufficient to "push" the desired current through the device under test and the connecting test leads. The overload capacity, represented by multiples of rated current, versus TIME ON and TIME OFF are given on the next page.

%Rated Current	Maximum Time ON	Minimum Time OFF
100 (1x)	15 minutes	30 minutes
150 (1.5x)	6 minutes	13 minutes
200 (2x)	3 minutes	8 minutes
250 (2.5x)	1 minute	6 minutes
300 (3x)	30 seconds	4 minutes
400 (4x)	7 seconds	2 minutes

Model CB-832 also can be used continuously for any reasonable length of time at 70.7% of the current rating of the output terminal.

EXAMPLE:
Consider the terminal rated at 500 amperes:

a. 500 amperes may be drawn at any voltage from 0-3.5 volts for 15 minutes provided the test set is subsequently de-energized for 30 minutes.

b. 353.5 amperes (70.7% of 500 amperes) may be continuously drawn at any voltage from 0-3.5 volts for any reasonable length of time.

c. The following overload currents may be drawn at any voltage from zero to maximum volts for the Time ON indicated, followed by the indicated Time OFF. The maximum output voltage available when the current rating of the output terminal is exceeded (overloaded) will be less than the rated value due to the regulation of the transformer in the test set. For example, when drawing 750 amperes from the 500 ampere terminal, the maximum voltage available is approximately 2.9 volts.

500 Ampere	Time ON	Time OFF
750 amperes	6 minutes	13 minutes
1000 amperes	3 minutes	8 minutes

It should be noted that because of the impedance of the device under test and the connecting test leads, the maximum practical test current available from the terminal rated 500 amperes is approximately 1000 amperes. Higher currents are usually available from the terminal rated 500 amperes; HOWEVER, these higher currents are available only for very short durations as illustrated in the overload capacity table above. For example, it is possible to get 1800 amperes from this terminal through a typical 225 ampere molded case circuit breaker for an instantaneous trip test.

SECTION III

TEST PROCEDURES

MAINTENANCE OF MOTOR OVERLOAD RELAYS

The prime function of the motor overload relay is to prevent operation of a motor for too long a period of time when an overload condition exists.

In general, motor starters are applicable to a given horsepower range of motors. The voltage and current requirements of the application will "size" the starter under NEMA requirements, but the actual starting current, running current and ambient temperature will determine the overload relay rating required to protect the motor without nuisance tripping.

Selection of the properly rated overload relay can be made by reference to tables or charts supplied by the manufacturer of the overload relays and motors. Whenever a motor trips out, it is poor practice to uprate the overload relay indiscriminately; the motor may actually be working under an overload condition or the overload relay may be operating improperly. Uprating the overload relay could permit an overload to continue, resulting in deterioration of the motor insulation and reduction in motor life. Therefore, careful analysis should be made as to the cause of the nuisance trip before changing the rating of the overload relay.

Operating characteristics of the motor overload relay should be verified at regular intervals. Typical practice dictates inspection of overload relays at periods of one to two years, with an actual test of tripping time to be made at intervals of two years. The test interval can vary with the type of service involved and the importance of the motor to process or production.

Motor overload relays incorporate an element which actuates a set of contacts connected to the motor control circuit. These contacts open the circuit of the holding coil in the motor starter and interrupt the power to the motor.

In general, there are three types of motor overload relays in use:

1. Thermal - melting alloy or solder pot
2. Thermal - bimetallic strip
3. Electromagnetic

In thermal type relays, time-current characteristics are obtained by the thermal properties of the melting alloy or bimetallic strip. In the magnetic type, a damped plunger or moving iron device is used to produce time delays.

1. Thermal - melting alloy or solder pot

In this type, tripping is the result of heat generated by the motor load current passing through a "heater" in the overload relay. This overload relay consists of a brass shaft which is surrounded by solder. Fixed to one end of the shaft is a small ratchet wheel.

As long as the solder is solid, this assembly is immobile. When the motor control circuit contacts are closed, a spring is held compressed by the immobility of the ratchet wheel. An overloaded condition in the motor increases the current through the heater, thus melting the solder and releasing the energy in the spring. This interrupts the circuit of the holding coil in the motor starter and shuts down the motor.

The starter may be reset only after the temperature of the heater has cooled sufficiently to permit the solder to solidify and again make the ratchet and shaft immobile. Reset is usually accomplished by an external pushbutton on the face of the starter. Many heaters offer a selection of either manual or automatic reset.

2. Thermal - bimetallic strip

This type uses a bimetallic strip - two pieces of dissimilar metal bonded together. An increase in heat will cause movement of this bimetallic unit and eventually open a set of contacts in the motor control circuit, thus opening the holding coil circuit and shutting down the motor.

The principle of operation is the same as the melting alloy type. When the bimetallic element has cooled sufficiently, the motor control circuit may be reset either manually or automatically.

3. Electromagnetic

In this type of motor overload relay, a damped plunger or moving iron device is used to produce the delays required and initiate the trip signal to the interrupting device. The most common type of magnetic overload relay utilizes a plunger or iron core piston which extends from an oil filled dashpot into the operating coil of the relay.

When the electromagnetic field produced by the operating coil is strong enough, the piston moves through the oil and opens the contacts of the relay. A time-delay is achieved by the oil in the dashpot, retarding the movement of the piston. Usually magnetic overload relays with oil dashpots have facilities which permit adjusting their minimum operating current (pick-up point) and their time delay characteristics.

PLANNED MAINTENANCE PROGRAM

A scheduled program for maintenance of motor overload relays consists primarily of "good housekeeping" in conjunction with visual inspections and electrical tests. A brief outline is given below:

1. Clean

All types of motor overload relays should be cleaned periodically to ensure continued, reliable operation. It is possible for dirt or dust, created by conditions in the plant, to prevent parts of the relay from moving. These same conditions can also prevent the proper dissipation of normal heating, resulting in unnecessary operation of thermal type overload relays.

2. Tighten Connections

This is particularly important in thermal overload relays. Loose electrical connections can cause extra heat which may result in a nuisance operation of the relay.

3. Inspect Heater Size

Determine that the specified heater is used in thermal overload relays. Too often, oversized heaters are arbitrarily installed to eliminate unexplained trips. Actually, the original heaters may have oxidized after a period of time and become smaller in cross section. In that event, the heat required to operate the relay is provided by a smaller amount of current than that intended by the original design. This may make the relay trip prematurely and the heater appear undersized.

4. Inspect Settings (Where applicable)

Most magnetic overload relays have adjustable settings for minimum operating current and time delay characteristics. These should be adjusted to the specified settings.

5. Test

The motor overload relay should be subjected to a simulated overload and the tripping time measured. This should be compared to the manufacturer's specifications or the relay's time curves to make certain that the relay is operating properly. A tolerance of $\pm$ 15% is usually acceptable. If the relay's curves or specifications are not available, it is suggested that the Heat Damage Curve of the motor be used as a guide for maximum trip time at 300% of motor full load current.TIME DELAY OF MOTOR OVERLOAD RELAYS

TIME DELAY

1. Set-up CB-832 with:
   a. POWER ON/OFF Switch in OFF position (instrument displays off).
   b. OUTPUT CONTROL knob at minimum **'0'** position.
   C. OUTPUT MODE Switch in center OFF position.

2. Connect one end of a high-current lead to one side of thermal element or current coil in overload relay. Connect other end of this lead to the COMMON terminal of test set.

3. Connect one end of second high-current lead to other side of thermal element or current coil in overload relay. Connect other end of this lead to the appropriate output terminal (see SELECTION OF OUTPUT TERMINAL).

4. Connect test set to suitable single-phase power supply.

5. Turn test set on with POWER ON/OFF Switch (instrument displays should light).

6. Use RANGE Switch to select ammeter range so test current will be near full scale and no less than 10% of full scale.

7. Put ammeter DISPLAY MODE Switch in MEMORY position.

8. Connect a pair of light leads (timer leads) from Normally Closed Contacts or Normally Open Contacts of overload relay to binding posts of test set labeled CONTACTS.

9. Select appropriate timer STOP MODE.

10. Select desired timer display mode and range.

11. Rotate OUTPUT CONTROL knob clockwise and momentarily press OUTPUT MODE Switch in MOMENTARY and release. Observe current reading retained by ammeter.

12. Continue to rotate OUTPUT CONTROL knob clockwise while jogging (repeatedly moving to MOMENTARY position and releasing) OUTPUT MODE Switch until desired test current is reached. Suggested test current is three times (3x) the rating of thermal relays or three times (3x) the pick-up current of magnetic relays.

If the relay utilizes a high impedance thermal element or operating coil and the desired test current cannot be reached, transfer output lead to the next higher voltage (lower current) terminal, and repeat Steps 11 and 12. If test current is still not reached, transfer output lead to terminal labeled 25A, and repeat Steps 11 and 12 (see SELECTION OF OUTPUT TERMINAL).

NOTE: Before starting test, allow time for thermal element to cool; or in the case of magnetic overload relays, for the piston to reset. Incorrect tripping time may otherwise result.

13. Put ammeter DISPLAY MODE in NORMAL position.

14. Start test by moving OUTPUT MODE Switch to MAINTAIN position.

NOTE: Test current may decrease (fall off) during the test because the resistance or impedance of the test circuit increases as it heats up. Rotate OUTPUT CONTROL knob clockwise to keep test current at desired value.

15. When overload relay trips, timer stops and output is de-energized. Timer indicates total elapsed time of the test in seconds or cycles.

16. Turn test set OFF with POWER ON/OFF Switch.

17. Record test results.

IMPORTANT

In order to obtain accurate tripping times with some types of magnetic overload relays, particularly those using high viscosity oil, it may be necessary to "preheat" the relay by running rated current through the relay for a few minutes.

INSTANTANEOUS ELEMENT

1. Set-up CB-832 with:
   a. POWER ON/OFF Switch in OFF position.
   b. OUTPUT CONTROL knob at minimum, **'0'** position.
   C. OUTPUT MODE Switch in center OFF position.

2. Connect one end of a high-current lead to one side of instantaneous element in overload relay. Connect other end of this lead to the COMMON terminal of test set.

3. Connect one end of second high-current lead to other side of instantaneous element in overload relay. Connect other end to the appropriate output terminal (see SELECTION OF OUTPUT TERMINAL 4).

4. Connect test set to suitable single-phase power supply.

5. Turn test set on with POWER ON/OFF Switch (instrument displays should light).

6. Use RANGE Switch to select ammeter range so test current will be near full scale and no less than 10% of full scale.

7. Put ammeter DISPLAY MODE in MEMORY position.

8. Connect a pair of light leads (timer leads) from Normally Closed Contacts or Normally Open Contacts of overload relay to binding posts of test set labeled CONTACTS.

9. Select appropriate timer STOP MODE.

10. Select desired timer display mode and range.

11. Rotate OUTPUT CONTROL knob clockwise and momentarily press OUTPUT MODE Switch in MOMENTARY and release. Observe current reading retained by ammeter.

NOTE: If the relay utilizes a high impedance instantaneous element and the desired test current cannot be reached, transfer output lead to the next higher voltage, lower current terminal, and repeat Step 11.

12. Continue Step 11 until overload relay trips. Observe current reading retained on

ammeter. Timer indicates elapsed time of test in cycles or seconds.

NOTE: To avoid tripping error caused by interference of time delay element, allow thermal element to cool; or in the case of magnetic overload relays, for the piston to reset.

13. Repeat test, starting with OUTPUT CONTROL knob at position just below trip current of instantaneous element observed in Step 12.

14. When overload relay trips, timer stops and output is de-energized. Current reading is retained on ammeter. Timer indicates elapsed time in seconds or cycles.

15. Turn test set OFF with POWER ON/OFF Switch.

16. Record results.

IMPORTANT

Refer to manufacturer's instructions for instantaneous trip time. If increasing test current does not decrease tripping time, current at which minimum tripping time was first observed is the instantaneous trip current value. Additionally, the test method outlined above is sometimes referred to as the "jogging" or "step" method. For nearly all applications, this method works best; however, there is another method referred to as the "run-up" method. Instead of the OUTPUT MODE Switch being in the MOMENTARY position, it is placed in the MAINTAIN position and the ammeter is placed in the NORMAL position. When the output is initiated, rotate OUTPUT CONTROL knob clockwise and observe current reading on ammeter. When the device trips, record trip current. If this method is used, it should be noted that the device is being heated with continuous current, and it is hard on the variable autotransformer windings and brush(es) (can cause premature wear-down of the brush(es) and carbon buildup - see SERVICE DATA).

MAINTENANCE OF MOLDED CASE CIRCUIT BREAKERS

The molded case circuit breaker essentially consists of two separate elements. One element is a set of contacts and suitable mechanical linkage for manual operation of the breaker as a switch in an electrical circuit. The other element is a device that senses and reacts to an overload or short circuit. Normally, the time delay overload device is thermal and the instantaneous overload device, when supplied, is magnetic. The thermal element usually uses a bimetallic strip; two pieces of dissimilar material bonded together. An overload causes an increase in heat which will result in moving the bimetallic unit and eventually trip the circuit breaker. The magnetic element operates with no intentional time delay to provide instantaneous protection against high magnitude faults.

PLANNED MAINTENANCE PROGRAM

A scheduled program for maintenance of molded case circuit breakers consists primarily of "good housekeeping" in conjunction with visual inspections and electrical tests. A brief outline is given below:

1. Clean

All types of molded case circuit breakers should be externally cleaned so that the heat produced in normal operation can be dissipated properly. It is possible for dirt or dust caused by normal plant conditions to accumulate and prevent proper dissipation of heat, resulting in a nuisance operation of the breaker.

2. Tighten Connections

This is particularly important because loose electrical connections can cause extra heat which may result in an unnecessary operation of the breaker.

3. Test

The molded case circuit breaker should be subjected to a simulated overload and the tripping time measured. This is important because after a period of inactivity, the overload device may become stiff or inoperable. The only way to determine this condition and eliminate the stiffness is to electrically operate the breaker on a periodic basis. Manually opening and closing the main contacts of the breaker does not move any of the mechanical linkage associated with the overload device. Testing may be as often as every 6 months or as long as every three or four years, depending upon conditions where the breaker is installed.

THERMAL ELEMENT

1. Set-up CB-832 with:
   a. POWER ON/OFF Switch in OFF position (instrument displays OFF).
   b. OUTPUT CONTROL knob at minimum, **'0'** position.
   c. OUTPUT MODE Switch in center OFF position.

2. Connect one end of a high-current lead to one pole of circuit breaker. Connect the other end of this lead to the COMMON terminal of test set.

3. Connect one end of the second high-current lead to the other side of the same pole of the circuit breaker. Connect other end of this lead to the appropriate output terminal (see SELECTION OF OUTPUT TERMINAL).

4. Connect test set to suitable single-phase power supply.

5. Turn test set on with POWER ON/OFF Switch (instrument displays should light).

6. Use RANGE Switch to select ammeter range so test current will be near full scale and no less than 10% of full scale.

7. Put ammeter DISPLAY MODE Switch in MEMORY position.

8. Place timer STOP MODE Switch in CURRENT position.

9. Select desired timer display mode and range.

10. Rotate OUTPUT CONTROL knob clockwise and momentarily press OUTPUT MODE Switch in MOMENTARY and release. Observe current reading retained by ammeter.

11. Continue to rotate OUTPUT CONTROL knob clockwise while jogging (repeatedly moving to MOMENTARY position and releasing) OUTPUT MODE Switch until desired test current is reached. Suggested test current is three times (3x) the rating of the circuit breaker.

    If desired test current is not reached with OUTPUT CONTROL knob at maximum clockwise rotation, return knob to zero and transfer output lead to the next higher voltage/lower current terminal. Proceed with current

adjustment as in Steps 10 and 11 (see SELECTION OF OUTPUT TERMINAL).

NOTE: Before starting test, allow time for the thermal element to cool, otherwise incorrect tripping time may result.

12. Put ammeter DISPLAY MODE in NORMAL position.

13. Start test by moving OUTPUT MODE Switch to MAINTAIN position.

NOTE: Test current may decrease (fall off) during the test because the resistance or impedance of the test circuit increases as it heats up. Rotate OUTPUT CONTROL knob clockwise to keep test current at desired value.

14. When circuit breaker trips, timer stops and output is de-energized. Timer indicates total elapsed time of the test in seconds or cycles.

15. Turn test set OFF with POWER ON/OFF Switch.

16. Record test results on Test Record Card.

IMPORTANT

Some types of circuit breakers are intended to trip only under high current fault condition, usually ten times (10x) rated current. They have only instantaneous characteristics and therefore will not trip using usual procedure described above.

INSTANTANEOUS ELEMENT

1. Set-up CB-832 with:
   a. POWER ON/OFF Switch in OFF position. (instrument displays OFF)
   b. OUTPUT CONTROL knob at minimum, **'0'** position.
   c. OUTPUT MODE Switch in center OFF position.

2. Connect one end of high-current lead to one pole circuit breaker. Connect the other end of this lead to the COMMON terminal of test set.

3. Connect one end of second high-current lead to the other side of the same pole of the circuit breaker. Connect other end of this lead to the appropriate output terminal (see SELECTION OF OUTPUT TERMINAL).

4. Connect test set to suitable single-phase power supply.

5. Turn test set on with POWER ON/OFF Switch (instrument displays should light).

6. Use RANGE Switch to select ammeter range so test current will be near full scale and no less than 10% of full scale.

7. Put ammeter DISPLAY MODE Switch in MEMORY position.

8. Place timer STOP MODE Switch in CURRENT position.

9. Select desired timer display mode and range.

10. Rotate OUTPUT CONTROL knob clockwise and momentarily press OUTPUT MODE Switch in MOMENTARY release. Observe current reading retained by ammeter.

    If desired test current is not reached with OUTPUT CONTROL knob at maximum clockwise rotation, return knob to zero and transfer output lead to the next higher voltage/lower current terminal. Proceed with current adjustment as in Step 10 (see SELECTION OF OUTPUT TERMINAL).

11. Continue Step 10 until circuit breaker trips. Observe current reading retained by ammeter. Timer indicates elapsed time of test in seconds or cycles.

NOTE: To avoid tripping error caused by time delay element over heating, allow time for it to cool.

12. Repeat test, starting with OUTPUT CONTROL knob at position just below trip current of instantaneous element observed in Step 11.

13. When circuit breaker trips, timer stops and output is de-energized. Current reading is retained on ammeter. Timer indicates elapsed time in seconds or cycles.

14. Turn test set OFF with POWER ON/OFF Switch.

15. Record results.

IMPORTANT

Refer to manufacturer's instructions for instantaneous trip time. If increasing test current does not decrease tripping time, current at which minimum tripping time was first observed is the instantaneous trip current value. Additionally, the test method outlined above is sometimes referred to as the "jogging" or "step" method. For nearly all applications, this method works best; however, there is another method referred to as the "run-up" method. Instead of the OUTPUT MODE Switch being in the MOMENTARY position, it is placed in the MAINTAIN position and the ammeter is placed in the NORMAL position. When the output is initiated, rotate OUTPUT CONTROL knob clockwise and observe current reading on ammeter. When the device trips, record trip current. If this method is used, it should be noted that the device is being heated with continuous current, and it is hard on the variable autotransformer windings and brush(es) (can cause premature wear-down of the brush(es) and carbon buildup - see SERVICE DATA).

GROUND FAULT ELEMENT

1. Set-up CB-832 with:
   a. POWER ON/OFF Switch in OFF position. (instrument displays OFF)
   b. OUTPUT CONTROL knob at minimum, **'0'** position.
   c. OUTPUT MODE Switch in center OFF position.

2. Connect one end of a high-current lead to one pole of ground fault circuit breaker. Connect other end of this lead to the COMMON terminal of test set.

3. Connect one end of second high-current lead to the other side of the same pole of the ground fault circuit breaker. Connect the other end of this lead to the appropriate output terminal (see SELECTION OF OUTPUT TERMINAL).

4. Connect test set to suitable single-phase power supply.

5. Turn test set on with POWER ON/OFF Switch (instrument displays should light).

6. Use RANGE Switch to select ammeter range so test current will be near full scale and no less than 10% of full scale.

7. Put ammeter DISPLAY MODE in MEMORY position.

8. Place timer STOP MODE Switch in CURRENT position.

9. Select desired timer display mode and range.

10. Rotate OUTPUT CONTROL knob clockwise and momentarily press OUTPUT MODE Switch in MOMENTARY and release. Observe current reading retained on ammeter.

11. Continue to rotate OUTPUT CONTROL knob clockwise while jogging (repeatedly moving to MOMENTARY position and releasing) OUTPUT MODE Switch until desired test current is reached. Suggested test current is one and one half times (1.5 x) the rating of the ground fault trip device.

    If desired, test current is not reached with OUTPUT CONTROL knob at maximum clockwise rotation, return knob to zero and transfer output lead to the next higher voltage/lesser current terminal. Proceed with current adjustment as in Steps 10 and 11 (see SELECTION OF OUTPUT TERMINAL).

12. Put ammeter DISPLAY MODE in NORMAL position.

13. Start test by moving OUTPUT MODE to MAINTAIN position.

14. When device trips, timer stops and output is de-energized. Timer indicates total elapsed time of the test in seconds or cycles.

15. Turn test set OFF with POWER ON/OFF Switch.

16. Record test results.

IMPORTANT

Refer to manufacturer's instructions for proper test current value and tripping time.

SECTION IV

SERVICE DATA

The test set utilizes straightforward circuits and components which require little or no service except for routine cleaning, tightening of connections, etc. The test set should be serviced in a clean atmosphere away from energized electrical circuits. The following maintenance is recommended:

Maintenance intervals depend on usage, but a maximum of every six months is recommended.

WARNING

Do not service unit unless it is disconnected from its power source.

1. Enclosure:

The enclosure can be cleaned with a soft cloth. If heavily soiled, the cloth can be dampened with an approved solvent that does not attack the finish or leave residue.

2. Control Panel:

The control panel can be wiped clean with a soft, dry cloth. Do not wipe the meter lenses with a cloth. If a breath of air will not remove dirt, brush it away lightly with a soft bristle instrument brush.

3. Variable Autotransformer:

The brushes are designed for long life, but should be checked periodically for excessive wear or chipping. The brushes must be changed before the brass brush holder touches the contact surface or serious damage will result. The brush contact area of the winding should be inspected for burning, pitting, dirt or debris. If necessary, burnish surface with burnishing tool, remove filings and clean surface with a swab moistened with alcohol (100% solution).

4. Other Components:

Check all knobs, printed circuit boards, screws, fasteners, connections and terminals for tightness and proper position. Remove dust with a soft brush and breath of air. Output terminal connection tightness is particularly important. If they become loose, excessive heating of the terminals and poor current output will result.

5. Insulation:

Check wiring and other insulated components for burning, cracking or other damage.

IMPORTANT NOTE

Do not use lubricants or solvents of any kind in the test set except as specifically recommended.

SERVICE AND REPAIR ORDER INSTRUCTIONS

If factory service is required or desired, contact the factory for return instructions.

A Service & Repair Order (SRO) number will be assigned for proper handling of the unit when it arrives at the factory.

If desired, a letter with the SRO number and instructions can be provided.

Provide the factory with model number, serial number, nature of the problem or service desired, return address, your name, and where you can be reached should the factory need to contact you.

A purchase order number, cost limit, billing, and return shipping instructions may also be provided if desired.

National Bureau of Standards traceable calibration and certification of two types is available, if desired, at additional cost:

Class One — A certificate is provided verifying the traceability and calibration of the equipment.

Class N — That which is required for nuclear power plants. A certificate of traceability and calibration along with "as found" and "as left" data are provided.

If an estimate is requested, provide the name and contact information of the person with approval/disapproval authority.

If damage or malfunction is suspected or repairs deemed necessary, consult a Multi-Amp Corporation Representative for assistance if it is unclear what course of action is needed. Please provide model and serial number when making inquiries.

Pack the equipment appropriately to prevent damage during shipment. If a reusable crate or container is used, the unit will be returned in it if the container is in suitable condition.

Put the SRO number on the address label of the shipping container for proper identification and faster handling at the factory.

NOTE: Ship the equipment without instruction manuals or nonessential items such as test leads, spare fuses, etc. These items are not needed to conduct repairs.

PREPARATION FOR RESHIPMENT

Save the shipping container for future use. The shipping container your unit came in is designed to withstand the normal bumps and shocks of shipping via common commercial carrier. For example, you may wish to reship your unit to Multi-Amp for annual calibration certification.

OPERATIONAL ERRORS/TROUBLESHOOTING

Some operational errors will cause the operator to suspect a test set malfunction. Some examples of these with common causes are as follows. Some basic component failures and malfunctions are also identified.

1. Difference in MEMORY/NORMAL ammeter readings:

Remember that the MEMORY mode is for taking instantaneous peak readings and not

for retaining continuous readings after the unit deinitiates. If used for continuous readings, an error will result. The NORMAL mode is calibrated to read RMS current. Do not switch from NORMAL to MEMORY to retain a reading or you will get a peak reading instead. The MEMORY and NORMAL readings will be nearly equal under normal conditions if the output current is maintained for several seconds after the meter is switched to the MEMORY position. The test set may need to be calibrated if the difference is very great.

2. No output current reading on the ammeter but the OUTPUT ON lamp is lighted:

   a. Current output test circuit is open.
   b. Fuse F2 has failed.
   c. CT is open or CT circuit connector has come loose at the printed circuit board (PCB).

3. Power on, no instruments lighted:

   a. Power ON/OFF Switch (CB1) has failed.
   b. Fuse F1 has failed.
   c. Power supply assembly or RF1 filter has failed.

4. Power on, instruments lighted, unit will not initiate:

   a. Improper timer stop mode selection for desired test.
   b. Output test circuit open.
   c. OUTPUT MODE Switch assembly (Maintain/OFF/Momentary) is faulty or its connector has come loose from the PCB.
   d. Triac failure.

5. Same as above, will not initiate in N.O. or N.C. Contacts mode:

   a. Faulty test leads.
   b. Incorrect test scheme for stop mode selected.
   c. Contacts being monitored are in incorrect position for stop mode selected.
   d. Contacts monitoring circuit has failed. Commonly caused by connecting contacts binding posts to an energized circuit.
   e. Contacts binding post connector has come loose at PCB.

6. Upon completion of output circuit, current appears on ammeter, timer does not initiate:

a. Initiate switch has been left in Maintain position after a test has been completed. The OUTPUT MODE Switch must always be returned to the off position when a test is completed or discontinued.

7. Power on, instrument displays lighted, either or both instruments will not function when unit is initiated:

   a. Failure in 15VDC power supply circuitry.
   b. Failure of protective diodes in current input or display section of ammeter.

NOTE: Refer to other example conditions before assuming these failures.

WARRANTY

Multi-Amp Corporation warrants to the original purchaser that the product is free of defects in material and workmanship for a period of one (1) year from date of shipment. This warranty is limited and shall not apply to equipment which has damage, or cause of defect, due to accident, negligence, improper operation, faulty installation by the purchaser, or improper service or repair by any person, company or corporation not authorized by Multi-Amp Corporation.

Multi-Amp Corporation will, at its option, either repair or replace those parts and/or materials that it deems to be defective. Any costs incurred by the purchaser for the repair or replacement of such parts and/or materials shall be the sole responsibility of the original purchaser.

THE ABOVE WARRANTY IS IN LIEU OF ALL OTHER WARRANTIES, EITHER EXPRESSED OR IMPLIED ON THE PART OF THE MULTI-AMP CORPORATION, AND IN NO EVENT SHALL THE MULTI-AMP CORPORATION BE LIABLE FOR THE CONSEQUENTIAL DAMAGES DUE TO THE BREACH THEREOF.



S1 - RANGE SWITCH

POS	FUNCTION
1	20A
2	200A
3	2000A
4	20KA

S2 - TIMER MODE SWITCH

POS	FUNCTION
1	CYCLE
2	SECONDS

S3 - INITIATE SWITCH

POS	FUNCTION
1	MAINTAIN
2	OFF
3	MOMENTARY

S4 - DISPLAY MODE SWITCH

POS	FUNCTION
1	NORMAL
2	MEMORY



ELD

DWG NO 19233D			
REV	ECN	DATE	REMARKS
1	14765	2 6 84	
2	[illegible]	[illegible]	
3	15284	7 15 87	
4	[illegible]	[illegible]	
5	19455	6 21 89	
6	21089	10 21 87	
7	22175	8 16 89	
8	23765	7 15 91	
9	24055	12 3 91	
10	25137	3 29 93	
11	25543	9/24/93	ADDED GRN STRAP AT T2

ITEM	PART NO.	DESCRIPTION	QTY
R4	4635	RESISTOR 1.0K Ω 0.1%	1
T2	8587	TRANSF. OUTPUT	1
T1	9307	TRANSF. VARIABLE	1
--	2130	KNOB RANGE SWITCH	1
--	9337	POWER SUPPLY ASS'Y. 240V.	1
S5 *	8125	SWITCH STOP RANGE	1
S3	9067	INITIATE ASS'Y.	1
S6 *	8124	SECONDS MODE	1
S4 *		DISPLAY MODE	1
S2 *		TIMER MODE	1
S1 *	8118	SWITCH RANGE	1
R3	7722	POT 2.0KΩ 10% 25 TURN	1
R1	2535	RESISTOR 47Ω 10% 1W.	1
Q1	4922	TRIAC	1
L1	8856	LAMP OUTPUT	1
⚠	9343	INSTR. & CONTROL ASS'Y.	1
FL1	6344	LINE FILTER 120V.	1
F1	981	FUSE 1/8A 250V.	1
F2,3	9312	12A 250V. TIME DELAY	2
F1-3	949	FUSE HOLDER	3
--	169	BINDING POST CONTACTS	2
CT1	9305	CURRENT TRANSDUCER	1
CB1	9873	CIRCUIT BREAKER 20A 250V. 1P	1
C1	8329	CAPACITOR .01 μfd 250V.	1

* PART OF INSTR. & CONTROL ASS'Y. 9343

⚠ S/N 32300 & UP

S5 - STOP MODE SWITCH

POS.	FUNCTION
1	NORM. OPEN
2	NORM. CLOSED
3	CURRENT

S6 - SECONDS RANGE SWITCH

POS.	FUNCTION
1	.01 SEC.
2	.001 SEC.

multi-amp CORPORATION
4271 BRONZE WAY, DALLAS, TEXAS 75237 (214) 333 3201

TOLERANCES DECIMAL ± .010 FRACTIONAL ± 1/64 UNLESS NOTED | DWN RMD | APPD [illegible] | SCALE NONE | CHKD | DATE [illegible] | SH 1 OF 1

TITLE SCHEMATIC CIRCUIT BREAKER TEST SET

PART NO CB-832-115 | DWG NO 19233D | REV 11

THE DEVICE DEPICTED AND DESCRIBED HEREON EMBODIES PROPRIETARY DESIGN OWNED BY MULTI AMP CORP. ALL DESIGN, MANUFACTURING, REPRODUCTION, SALES AND PATENT RIGHTS REGARDING THIS DEVICE OR DRAWING ARE RESERVED, EXCEPT WHERE EXPLICIT RIGHT IS GRANTED IN WRITING.



S1 - RANGE SWITCH

POS.	FUNCTION
1	20A
2	200A
3	2000A
4	20KA

S2 - TIMER MODE SWITCH

POS.	FUNCTION
1	CYCLE
2	SECONDS

S3 - INITIATE SWITCH

POS.	FUNCTION
1	MAINTAIN
2	OFF
3	MOMENTARY

S4 - DISPLAY MODE SWITCH

POS.	FUNCTION
1	NORMAL
2	MEMORY



DWG. NO. 19234 D			
REV.	E.C.N.	DATE	REMARKS
1	14765	2-6-84	
2	15059	4-10-84	MOVED L1 & R2 LEAD
3	15269	7-26-84	
4	15668	7-31-84	
5	18855	2-21-86	
6	21069	10 21 87	
7	22175	8 16 89	
8	23765	7 15 91	
9	24055	12 3 91	
10	25137	3 29 93	
11	25543	9/24/93	ADDED GND SYMB AT T2

ITEM	PART NO.	DESCRIPTION	QTY.
R4	4635	RESISTOR 1.0K Ω 0.1%	1
T2	8587	TRANSF. OUTPUT	1
T1	9307	TRANSF. VARIABLE	1
- -	2130	KNOB RANGE SWITCH	1
- -	8616	POWER SUPPLY ASS'Y. 240V	1
S5 *	8125	SWITCH STOP RANGE	1
S3	9067	INITIATE ASS'Y.	1
S6 *	8124	SECONDS MODE	1
S4 *		DISPLAY MODE	1
S2 *		TIMER MODE	1
S1 *	8118	SWITCH RANGE	1
R3	7722	POT 2.0K Ω 10% 25 TURN	1
R1	2535	RESISTOR 47 Ω 10% 1W.	1
Q1	4922	TRIAC	1
L1	8856	LAMP OUTPUT	1
⚠	9343	INSTR. & CONTROL ASS'Y.	1
FL1	9344	LINE FILTER 120 V.	1
F1	981	FUSE 1/8 A 250 V.	1
F2,3	9312	12A 250V. TIME DELAY	2
F1-3	949	FUSE HOLDER	3
- -	169	BINDING POST CONTACTS	2
CT1	9308	CURRENT TRANSDUCER	1
CB1	9873	CIRCUIT BREAKER 20A 250V 1P	1
C1	8329	CAPACITOR .01 μFd 250 V.	1

* PART OF INSTR. & CONTROL ASS'Y. 9343

⚠ S/N 32300 & UP

S5 - STOP MODE SWITCH

POS.	FUNCTION
1	NORM. OPEN
2	NORM. CLOSED
3	CURRENT

S6 - SECONDS RANGE SWITCH

POS.	FUNCTION
1	.01 SEC.
2	.001 SEC.

multi-amp CORPORATION
4271 BRONZE WAY, DALLAS, TEXAS 75237 (214) 333-3201

TOLERANCES: DECIMAL ± .010 FRACTIONAL ± 1/64 UNLESS NOTED | DWN. ND | APPD. [illegible] | SCALE: NONE | CHKD. | DATE 11/16/93 | SH. 1 OF 1

THE DEVICE DEPICTED AND DESCRIBED HEREON EMBODIES PROPRIETARY DESIGN OWNED BY MULTI-AMP CORP. ALL DESIGN, MANUFACTURING, REPRODUCTION, SALES AND PATENT RIGHTS REGARDING THIS DEVICE OR DRAWING ARE RESERVED, EXCEPT WHERE EXPLICIT RIGHT IS GRANTED IN WRITING.

TITLE CB832 SCHEMATIC CIRCUIT BREAKER TEST SET

PART NO. CB-832-230 | DWG. NO. 19234 D | REV. 11

www.manualsplus.com
1000207